



**Cambridge Instruments
& Engg. Co.**

EST. 1963 · HOWRAH, INDIA

INSULATION TESTER · MOTOR-OPERATED

CIE/777

Mains-motor-driven insulation tester for sustained PI and dielectric absorption testing — 500V to 10,000V, no hand-cranking required.

UP TO 10000V

Motorised Insulation Tester

A universal, mains-motor-driven insulation tester for checking insulation and conductance under simulated operating conditions — sustains test voltage continuously, enabling genuine polarization index (PI) and dielectric absorption testing that hand-cranked instruments cannot sustain.

- **Mains-motor-driven** — no hand-cranking required
- **Sustained PI & DAR testing** — continuous voltage, any duration
- **Guard ring & guard terminal** — eliminates surface-leakage errors
- **Seasoned wooden body** — sunmica finish, detachable lid & lock
- **3-second response** — quick direct reading
- **6 rated voltages** — 500V to 10,000V, build-to-order

Manufactured in India since 1963 — trusted by MSEB, Indian Railways, WBSETCL, etc.



- M Motor-Driven** No hand-cranking required
- P PI & DAR** Sustained voltage testing
- V Up to 10000V** 6 rated voltages

01 Full Specification Sheet

PARAMETER	SPECIFICATION
Drive	Mains motor, 230 V, 50 Hz A.C.
Body	Seasoned wooden cabinet, sunmica finish, detachable lid, handle, lock
Scale Length	100 mm (approx.)
Accuracy	As per IS: 2992-1987
High Voltage Test	Min. 2kV or (rated V + 1)kV A.C. r.m.s., 1 min
Insulation Resistance Test	Better than 50 M Ω at 500V D.C.
Response Time	3 seconds
Rated Voltages	500V / 1000V / 2500V / 5000V / 10000V
500V Range Options	0-1000 M Ω
1000V Range Options	0-2000 M Ω
2500V Range Options	0-5000 · 0-10000 · 0-20000 M Ω
5000V Range Options	0-5000 · 0-10000 · 0-20000 · 50-50000 · 100-100000 M Ω
10000V Range Options	0-10000 · 0-20000 · 50-50000 · 100-100000 M Ω
Ordering	Build-to-order — specify voltage & resistance range
Dimensions (top cover)	14 × 10 × 10 inch (approx.)
Weight (top cover)	9 kg (approx.)
Warranty	12 months against manufacturing defects

02 Typical Applications

- Sustained PI testing on large rotating plant
- Power transformer insulation & DAR assessment
- HV cable and switchgear insulation testing
- Substation commissioning by EPC contractors

03 What's in the Box

- ✓ Mains cord, 2 metres
- ✓ 1 pair of H.V. testing leads

04 Optional Accessories

- + Rexine carrying case
- + 15-minute timer facility
- + Timer
- + Additional/special H.V. leads, 2m
- + Dual voltage & range option
- + Single voltage, dual range option

OFFICE

55, Ezra Street, 4th Floor, Yamuna Bhawan,
Kolkata 700001, West Bengal, India

WORKS

23/2, Maulana Abul Kalam Azad
Road, Howrah 71101, West
Bengal, India

CONTACT

+91 98300 91260
+91 98300 92117
cieinstruments@gmail.com

ONLINE

cieinstruments.in
Instruments for accuracy and
reliability since 1963.