



Cambridge Instruments
& Engg. Co.

EST. 1963 · HOWRAH, INDIA

INSULATION TESTER · MOTOR-CUM-HAND OPERATED

CIE/777 HM

Motor-cum-hand driven insulation tester - mains motor for PI testing, hand-crank backup for field use. Available in single-range configurations from 500V to 10,000V.

WOODEN BODY

Motor-cum-Hand Driven Insulation Tester

Combines mains-motor drive with a collapsible hand-crank backup in one instrument - the same sustained-voltage PI and dielectric absorption capability as the CIE/777, plus a centrifugal-governed hand crank for use where mains power is unavailable.

- **Motor + hand-crank backup** - works with or without mains
- **Sustained PI & DAR testing** - motor-driven mode
- **Collapsible generator handle** - specific to the HM variant
- **Centrifugal governor** - constant voltage in hand-crank mode
- **Guard terminal & infinity adjuster** - eliminates surface-leakage errors

Manufactured in India since 1963 - trusted by various State Electricity Boards, Indian Railways, cement and metal industries, and other sectors.



- M Motor + Hand** Works with or without mains
- P PI & DAR** Sustained voltage testing
- V 500-10000V** Available ranges, specify at order

01 Full Specification Sheet

PARAMETER	SPECIFICATION
Drive	Mains motor (230V, 50Hz A.C.) + collapsible hand-crank
Body	Seasoned wooden cabinet, sunmica finish, detachable lid, handle, lock
Scale Length	100 mm (approx.)
Accuracy	As per IS: 2992-1987
High Voltage Test	Min. 2kV or (rated V + 1)kV A.C. r.m.s., 1 min
Insulation Resistance Test	Better than 50 MΩ at 500V D.C.
Guard Terminal & Infinity Adjuster	Guard ring & guard terminal eliminate surface-leakage errors; infinity adjuster provided
Response Time	3 seconds
Range Configuration	Multiple range options available - specify at order
Dimensions (top cover)	14 × 10 × 10 inch (approx.)
Weight (top cover)	12 kg (approx.) - vs 9 kg for plain CIE/777
Warranty	12 months against manufacturing defects

Custom ranges and configurations can also be built against specific requirements.

02 Typical Applications

- Field testing where mains supply is uncertain
- Sustained PI & DAR testing (motor-driven mode)
- Remote substation and railway traction commissioning
- HV transformer and cable insulation assessment

03 What's in the Box

- ✓ Mains cord, 2 metres
- ✓ 1 pair of H.V. testing leads

04 Optional Accessories

- + Rexine carrying case
- + 15-minute timer facility
- + Additional/special H.V. leads, 2m
- + Dual voltage & range option
- + Single voltage, dual range option