



**Cambridge Instruments
& Engg. Co.**

EST. 1963 · HOWRAH, INDIA

INSULATION TESTER · MOTOR-OPERATED

CIE/777

Mains-motor-driven insulation tester for sustained PI and dielectric absorption testing - no hand-cranking required. Available in single-range configurations from 500V to 10,000V.

WOODEN BODY

Motorised Insulation Tester

A universal, mains-motor-driven insulation tester for checking insulation and conductance under simulated operating conditions

- sustains test voltage continuously, enabling genuine polarization index (PI) and dielectric absorption testing that hand-cranked instruments cannot sustain.

- **Mains-motor-driven** - no hand-cranking required
- **Sustained PI & DAR testing** - continuous voltage, any duration
- **Guard terminal & infinity adjuster** - eliminates surface-leakage errors
- **Seasoned wooden body** - sunmica finish, detachable lid & lock
- **3-second response** - quick direct reading

Manufactured in India since 1963 - trusted by various State Electricity Boards, Indian Railways, cement and metal industries, and other sectors.



- M Motor-Driven** No hand-cranking required
- P PI & DAR** Sustained voltage testing
- V 500-10000V** Available ranges, specify at order

01 Full Specification Sheet

PARAMETER	SPECIFICATION
Drive	Mains motor, 230 V, 50 Hz A.C.
Body	Seasoned wooden cabinet, sunmica finish, detachable lid, handle, lock
Scale Length	100 mm (approx.)
Accuracy	As per IS: 2992-1987
High Voltage Test	Min. 2kV or (rated V + 1)kV A.C. r.m.s., 1 min
Insulation Resistance Test	Better than 50 MΩ at 500V D.C.
Guard Terminal & Infinity Adjuster	Guard ring & guard terminal eliminate surface-leakage errors; infinity adjuster provided
Response Time	3 seconds
Range Configuration	Multiple range options available - specify at order
Dimensions (top cover)	14 × 10 × 10 inch (approx.)
Weight (top cover)	9 kg (approx.)
Warranty	12 months against manufacturing defects

Custom ranges and configurations can also be built against specific requirements.

02 Typical Applications

- Sustained PI testing on large motors and generators
- Power transformer insulation & DAR assessment
- HV cable and switchgear insulation testing
- Substation commissioning by EPC contractors

03 What's in the Box

- ✓ Mains cord, 2 metres
- ✓ 1 pair of H.V. testing leads

04 Optional Accessories

- + Rexine carrying case
- + 15-minute timer facility
- + Additional/special H.V. leads, 2m
- + Dual voltage & range option
- + Single voltage, dual range option